BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-16/2019-20 Dt:31-1-2020

MODIFIED APPROVED TENDER SCHEDULE –'B'

Item 04

Name of Work :-Providing Grill work to park in Kempegowda ward no:01 o Yelahanka sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Srl.Anjankumar Y.A	
				Rate	Rate in Words
1	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	54.99	5064.00	Five Thousand SixtyFour Only
2	KSRB14.6: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, sha[pe and colour with a minimum copressive strength of 281 kg per sqm over 50 mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials , labbour and HOM complete as per specifictions specification No KBS	Sqm	374.40	1026.00	One Thousand TwentySix Only
3	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge.	Nos	381.00	398.00	Three Hundred NinetyEight Only

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri.Anjankumar Y.A	
				Rate	Rate In Words
4	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6.	Sqm	52.56	79.90	SeventyNine Paise Ninety Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.